


Forward Proton Detector Detector Construction

Michael Strang


University of Texas at Arlington






Detector Needs

- Position resolution of 100 μ m
 - Beam dispersion and uncertainty in beam position make better resolution unnecessary
- Efficiency close to 100%
- Modest Radiation Hardness
 - Operates at 8σ from beam axis, 0.03 MRad yearly dose expected
- High Rate capability
 - Active at every beam crossing
- Low background rate
 - Insensitive to particles showering along beam pipe
- Small dead area close to the beam
 - Protons are scattered at very low angles, acceptance is very dependent on position relative to beam
- Scintillating Fiber detector meets these needs





Detector Setup


Six planes
 (u, u', x, x', v, v')
 of $800 \mu\text{m}$
 scintillating
 fibers
 ($'$) planes
 offset by $2/3$
 fiber




20 channels/plane(U, V)($'$)
 16 channels/plane(X, X')
 112 channels/detector
 18 detectors
 2016 total channels
 4 fibers/channel
 8064 fibers
 1 $250 \mu\text{m}$ LMB
 fiber/channel
 8 LMB fibers / bundle
 252 LMB bundles
 $80 \mu\text{m}$ theoretical
 resolution



4 fiber bundle
 fits well the
 pixel size of
 H6568 16 Ch.
 MAPMT




7 PMT's/detector
 16 $250 \mu\text{m}$ fibers
 each PMT



Detector Fibers



- Scintillating fiber is spliced to clear fiber
 - Increased halo background with scintillating only
 - Light output improved due to longer attenuation length of clear fiber
 - Cross talk is reduced



- Fibers produced by Bicron
 - 0.80 mm square multiclاد fiber emitting in blue λ
- Square fiber can only be polished using ice polishing method at FermiLab Lab 7
- After polishing fibers are inspected for deformity and cladding damage and repolished if needed

Detector Frames

- Cast at FermiLab Lab 5 plastics shop
- Original aluminum machined piece is molded and production pieces are cast in polyurethane



Splicing


- Splicing being completed at UTA
- Fibers spliced using a version of the MSU splicing machine modified for square fibers



- With proper setup, light transmission through splice point of over 90% possible
- Afterwards, splice point is sensitive to bending stresses so care must be taken
 - Shrink tubing cannot be used to strengthen splice due to space constraints

Frame Assembly


- Being completed at UTA
- Detector active area (17.42 mm from bottom) is marked on frame
- Four fibers have splice point aligned
- Splice point is aligned with mark in frame



- Bicon optical epoxy is used to secure the fibers into the frame once completely assembled. The glue cures overnight.


Trigger Scintillator

- With x' frame an additional step is needed because of trigger scintillator
 - Trigger scintillator is cut and glued to wave guide at FermiLab Lab 6
 - + Scintillator is coated with Aluminum at FermiLab Lab 7



Cookie Assembly


- After both sides of frame are completed the fibers can be glued into the cookies



- Detector is clamped to a vertical wooden backboard and proper distances are measured




- Fibers are secured with Bicon optical epoxy.




Phototube Testing

- At D0 DAB3, phototubes are tested using an LMB with a modified cookie
- The LMB pulses all 16 channels of the MAPMT simultaneously and ADC information is recorded for each channel
- The average ADC count of the 16 channels is used to bin the tubes in groups of 7 with spares and these bins are assigned to locations in the tunnel
- The LMB also strobes the L0 tubes and they are binned in groups of 4 with spares

Full Detector Assembly



- After arrival at FNAL, the inside edge of the U/V frames are cut and diamond polished at Lab 6 then aluminized at Lab 7
- The detector frames are assembled with care taken in alignment of U/V with the X into a block and secured with screws
- The bottom is cut and diamond polished then aluminized



Mapping


- The aluminized detector is disassembled and mapped using a 2 micron optical scanner
 - The aluminization helps light reflection to measure the edges of three overlapping fibers in each frame
- Each frame is measured in it's "native" coordinates. The locations where 3 fibers overlap are used to define an active channel
- Data is collected for alignment of frames with respect to each other and with respect to a common reference point in the pot
- This allows us to have a real pixel map for each detector

Cartridge Assembly

- The cartridge houses the detector and phototubes in the roman pot in the tunnel




- The cartridge bottom is installed in the tunnel and the detector is pushed to the bottom of the pot
- The Cartridge top fits over the bottom and is secured down causing good contact between the tubes and cookies



Detector Installation

- The cartridge bottom is installed in the tunnel and the detector is pushed to the bottom of the pot
- The Cartridge top fits over the bottom and is secured down causing good contact between the tubes and cookies
- The HV is tested to ensure that the splitter is working properly
- Signals are measured from the tubes using dark current to verify bad channels
- LMB signals are amplified and measured at the SCR using the DAQ



Status

- 8 detectors are installed in the tunnel
- 4 additional detectors are being finished at UTA and assembled for insertion in tunnel. Tubes are available for 10 detectors and installed
- 8 additional detectors will be constructed for insertion into tunnel next Summer for Phase II
- New subcomponent of FPD project is the Veto Counter located on the inside edge of Low Beta Quads at the beam pipe for more effective veto